Precision Communications Inc.

P.O. Box 298 Amory, MS 38821 662-256-3118 or 800-737-7357

Estimate

Estimate No. 13755 Date 7/30/2020

Bill To MADISON COUNTY EMA ALBERT JONES 125 W NORTH ST CANTON, MS 39046 Ship To MADISON COUNTY EMA ALBERT JONES 1633 WEST PEACE STREET CANTON, MS 39046

P.O. No.

Description	Qty	Rate	Total
SERVICE CONTRACT TO PROVIDE LABOR AT SITE FOR BI-ANNUAL INSPECTION:	1	18,159.50	18,159.50

FIRST SITE PM: WILL INCLUDE INSPECTION OF SPEAKER CLUSTER, SIREN CABINET, AND AC SERVICE FOR ANY SIGNS OF DAMAGE OR LOOSE HARDWARE. LOAD TEST BATTERIES FOR PROPER VOLTAGE. TEST BATTERY CHARGERS FOR PROPER VOLTAGE OUTPUT. TEST AMPS AND DRIVERS. CHECK ALL CONDUIT FOR WATER TIGHT CONNECTION AND ENTRANCE INTO CABINET, CHECK INTEGRITY OF LIGHTNING PROTECTION AND ANY CORROSION OF CONNECTIONS, OBSERVE POLE FOR ANY SHIFTING OR LEANING, SIREN CABINET: INSPECT FOR ANY FOREIGN MATERIAL OR RODENT INTRUSIONS, CLEAN ALL DRAIN HOLES AND SCREENS, EXAMINE ALL WIRING HARNESSES AND TERMINATIONS, AND PROPER CONNECTIONS. INSPECT ANTENNAS, COAX, AND RADIO TRANSMIT OUTPUT AND FREQUENCY DEVIATION AND RECEIVE LEVELS. CHECK FOR PROPER GROUNDING, SPEAKER ARRAY, ANTENNA BRACKET, CABINET BRACKET AND POLE GROUNDING. REPAIR OR REPLACE ANY PARTS OF NORMAL WEAR AND TEAR NOT TO EXCEED \$50.00.

ALSO INCLUDES LABOR TO CHECK THE INTEGRITY OF BOTH CENTRALERT CONTROLLERS AND ASSOCIATED RADIO EQUIPMENT. TEST SYSTEM COMPLETE FROM BOTH CONTROLLERS.

PRICE INCLUDES REPLACEMENT OF BATTERIES ONCE EVERY THREE YEARS WITH A THREE YEAR CONTRACT.

**THIS PRICE IS PER YEAR FOR THREE YEARS.

**THIS PRICE IS FOR 25 R4 WHELEN SIRENS PER YEAR WHICH IS \$726.38 PER SIREN

SECOND SITE PM: SIREN CABINET - INSPECT FOR ANY FOREIGN MATERIAL OR RODENT INTRUSIONS; CLEAN ALL DRAIN HOLES AND SCREENS; EXAMINE ALL WIRING HARNESSES AND TERMINATION FOR PROPER CONNECTIONS; CHECK RADIO TRANSMIT OUTPUT AND FREQUENCY DEVIATION AND RECEIVE LEVELS; CHECK GROUNDING; CHECK AC SERVICE FOR ANY SIGNS OF DAMAGE OR LOSE HARDWARE; LOAD TEST BATTERIES OR PROPER VOLTAGE OUTPUT; TEST AMPS AND DRIVER CIRCUITS; CHECK ALL CONDUIT FOR WATER TYPE CONNECTIONS AND ENTRANCE INTO CABINET; TEST ALL SIRENS REMOTELY FROM CENTRALERT CONTROLLERS TO ENSURE PROPER COMMUNICATION.