







**SITE GRADING PLAN**

- NOTES**
- SEE SITE PLAN FOR LOCATION & EXTENT OF UNDERCUT & BACKFILL FOR BUILDING. THE DEPTH OF UNDERCUT IN THE BUILDING AREA WILL EXTEND DOWN TO ELEVATION 211.8. THE OPERATIONS WILL PROVIDE A PER CLAY SAND UNIT PRICE FOR UNDERCUT, BACKFILL & CONSTRUCTION OF ADDITIONAL WORK, WHICH MAY BE REQUIRED BELOW THIS DEPTH.
  - ALL ASPHALT PAVEMENT AREAS TO HAVE A MINIMUM 0.3"-2" OF SELECT FILL OR STONING OVER THE EXISTING SUBGRADE BY THE SOIL ENGINEER, BEYOND THE BOTTOM OF THE PAVEMENT BASE COURSE.  
ALL PAVEMENT TO BE UNDERLAIN WITH AN 8" LAYER OF LIME TREATED SOILS. THE LIME TREATED LAYER IS INCLUDED IN THE 3"-5" LAYER OF SELECT FILL OR STONING NATURAL SOILS REQUIRED AT ASPHALT PAVEMENT.
  - LANDSCAPING FOR NEW OPERATIONS BUILDING TO BE SIMILAR TO EXISTING OFFICE.



NORTH

SINGLETON  
ARCHITECTS P.A.

A R C  
H + E  
C T S

POST OFFICE BOX 16259  
JACKSON, MS 39236-6259  
601-982-2362/601-511-2148 FAX

DATE: 3 JUNE 2013  
DRAWN: SK  
CHECKED: LS  
FILE: 1323 C1.5 CWS  
REV:

Project Name:  
A NEW OPERATIONS BUILDING FOR  
BEAR CREEK WATER ASSOCIATION  
JACKSON, MISSISSIPPI



Job no. 1323

Sheet No.  
**C 1.2**  
OF 5 SHEETS