



P.O. Box 298  
 Amory, MS 38821  
 Phone: 662-256-3118  
 Email: [precisioncommunicationsinc@gmail.com](mailto:precisioncommunicationsinc@gmail.com)

# ESTIMATE

Estimate No.: 18495  
 Date: 07/29/2024

Bill to:  
 ALBERT JONES  
 MADISON COUNTY EMA  
 125 W NORTH ST  
 CANTON, MS 39046

Ship to:  
 MADISON COUNTY EMA  
 ALBERT JONES  
 1633 WEST PEACE STREET  
 CANTON, MS 39046

P.O. No.

DESCRIPTION	QTY	RATE	AMOUNT
2024 SERVICE CONTRACT TO PROVIDE LABOR AT SITE FOR BI-ANNUAL INSPECTION:	1	19,270.00	19,270.00

FIRST SITE PM: WILL INCLUDE INSPECTION OF SPEAKER CLUSTER, SIREN CABINET, AND AC SERVICE FOR ANY SIGNS OF DAMAGE OR LOOSE HARDWARE. LOAD TEST BATTERIES FOR PROPER VOLTAGE. TEST BATTERY CHARGERS FOR PROPER VOLTAGE OUTPUT. TEST AMPS AND DRIVERS. CHECK ALL CONDUIT FOR WATER TIGHT CONNECTION AND ENTRANCE INTO CABINET, CHECK INTEGRITY OF LIGHTNING PROTECTION AND ANY CORROSION OF CONNECTIONS, OBSERVE POLE FOR ANY SHIFTING OR LEANING, SIREN CABINET: INSPECT FOR ANY FOREIGN MATERIAL OR RODENT INTRUSIONS, CLEAN ALL DRAIN HOLES AND SCREENS, EXAMINE ALL WIRING HARNESSSES AND TERMINATIONS, AND PROPER CONNECTIONS. INSPECT ANTENNAS, COAX, AND RADIO TRANSMIT OUTPUT AND FREQUENCY DEVIATION AND RECEIVE LEVELS. CHECK FOR PROPER GROUNDING, SPEAKER ARRAY, ANTENNA BRACKET, CABINET BRACKET AND POLE GROUNDING. REPAIR OR REPLACE ANY PARTS OF NORMAL WEAR AND TEAR NOT TO EXCEED \$50.00.

ALSO INCLUDES LABOR TO CHECK THE INTEGRITY OF BOTH CENTRALERT CONTROLLERS AND ASSOCIATED RADIO EQUIPMENT. TEST SYSTEM COMPLETE FROM BOTH CONTROLLERS.

\*\*CUSTOMER PROVIDES BATTERIES  
 \*\*THIS PRICE IS FOR YEAR FOR 2024  
 \*\*TECH TO CALL CUSTOMER FOR ANY REPAIRS >\$50 FOR ON-SITE APPROVAL

SECOND SITE PM: SIREN CABINET - INSPECT FOR ANY FOREIGN MATERIAL OR RODENT INTRUSIONS; CLEAN ALL DRAIN HOLES AND SCREENS; EXAMINE ALL WIRING HARNESSSES AND TERMINATION FOR PROPER CONNECTIONS; CHECK RADIO TRANSMIT OUTPUT AND FREQUENCY DEVIATION AND RECEIVE LEVELS; CHECK GROUNDING; CHECK AC SERVICE FOR ANY SIGNS OF DAMAGE OR LOSE HARDWARE; LOAD TEST BATTERIES OR PROPER VOLTAGE OUTPUT; TEST AMPS AND DRIVER CIRCUITS; CHECK ALL CONDUIT FOR WATER TYPE CONNECTIONS AND ENTRANCE INTO CABINET; TEST ALL SIRENS REMOTELY FROM CENTRALERT CONTROLLERS TO ENSURE PROPER COMMUNICATION.

- 
- Credit card payments will incur a 3% charge
  - Shipping cost(s) are calculated at time of shipment
  - This Estimate is good for 90 days from above date

	<b>Subtotal</b>	19,270.00
	<b>Sales Tax</b>	0.00
	<b>Total</b>	<b>\$19,270.00</b>